

## Mechanical Scissor Grab

### Product information

Designed to lift, move and release numerous types of slabs, blocks and single or double layer kerb packs safely on a building site or yard. Fully mechanically operated via the forklift (without the driver leaving the safety of his seat) or via an overhead crane / HIAB. An alternative of the ISG-5, this unit was introduced to secure smaller packs of bricks and blocks - to suit all requirements on site.

#### Standard Features

- Fixed internal pack height
- Profiled hooks for attachment of optional restraint net
- Fully automatic mechanism
- Segmented interchangeable rubber pads
- Painted bright orange for safety

#### Optional Features

- Restraint Net
- Fork Mounted Locating Yoke – refer to separate specification sheet



Part code

WLL  
ton

Jaw width  
mm

Weight  
kg

Delivery time

6221ISG6

2.5

500-970

210

2